No.	Items of work	Unit	Rate	Quantity	Cost
	Waste Weir Right R. L. 50·00.		Rs. a. p.		Rs.
1	Earthwork excavation hard soil mixed with jelly.	C.yd.	0 6 0	19	7
2	Concrete in surki mortar ...	C.ft.	0 4 0	215	54
3	Burnt stone in surki mortar or: ...				
3a	Burnt brick in surki mortar ...	„	0 5 0	309	97
4	Pointing with cement or surki plastering.	Sqr.	4 8 0	3·97	18
5	New stone work ...	C.yd.	1 12 0	41	72
6	Filling in jelly below apron ...	„	1 0 0	9	9
7	Burnt stone slabs 4" to 6" thick ...	S.ft.	0 5 0	151	47
8	Providing joggles ...	Each	0 8 0	6	3
9	Unforeseen items charges ...	Lump	sum	...	10
	Total Right Waste Weir ...	...	...	...	317
	Sluice R. L. 39·00.				
1	Earthwork excavation hard soil mixed with jelly.	C.yd.	0 6 0	112	42
2	Concrete in surki mortar ..	C.ft.	0 4 0	315	79
3	Burnt brick in surki mortar ...	„	0 4 6	1,337	376
4	Burnt stone slabs 4" to 6" thick, neatly dressed.	S.ft.	0 5 0	301	94
5	Drilling holes in slabs ...	Lump	sum		5
6	Plastering with surki mortar or ...				
6a	pointing with cement mortar.	Sqr.	4 0 0	11·81	47
7	Refilling the earth as per excavation ..	C.yd.	0 3 0	112	21
7a	Add ⅓ of gravel to be mixed for front slope.	„	0 8 0	34	17
8	Providing teak wooden plug with angle iron rod 2' x 2".	Each	20 0 0	1	20
9	Dismantling the old sluice and for forming approach and leading channels.	Lump	sum	....	20
	Total Sluice ...	...	...	...	721
	Total 2363+247+317+721= Rs. 3,648.	..	...	....	...

C. T. NARASIMHA IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification, dated 28th October 1933.

SUBJECT:—Restoring Besige Doddakere, Reg. No. 88 of Tiptur Taluk.

Attention of the public is drawn to the notification calling for tenders for the above work in pages 1368 and 1369, Part VI of the *Mysore Gazette*, dated 2nd November 1933.

2. Tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 2 P.M. of 27th November 1933.

3. An earnest money of Rs. 300 should accompany the tender.

Abstract Notification, dated 22nd October 1933.

SUBJECT:—Restoring the Breached Gowdihalli Tank R. No. 326 of Tumkur Taluk.

Attention of the public is drawn to notification, calling for tenders for the above work in pages 1367, and 1368, Part VI of the *Mysore Gazette*, dated 2nd November 1933.

The tenders will be received at the Office of the Executive Engineer, Tumkur Division, Tumkur, up to 2 P.M. of 27th November 1933.

3. An earnest money of Rs. 200 should accompany the tender.

Notice.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2 P.M. of 4th December 1933, for improving the left sluice below Maidala Amanikere, Tumkur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 30th June 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed, both in words and figures.

4. Each tender must be accompanied by a deposit of rupees 400 (four hundred) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for improving the left sluice channel below Maidanahalli Amanikere," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, Tumkur Division, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8 On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Percentage rates above or below the estimate amount will not be accepted.

10. No claims for enhanced rates will be entertained on any account after acceptance

11 The contractor will be dealt with in terms of the bond for any short progress or delay. In matters of all disputes about rate and measurements and quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and finally binding on the contractor.

12. Rates should be quoted both in words and figures for each item of work. Lumpsum provisions are subject to modification as per data worked out during the execution. For individual items of work under lumpsum provision, the rates tendered for similar items of work will be paid and for other items, the rates as per schedule of rates will be at the discretion of the Executive Engineer.

Abstract estimate of quantities of improving left channel below Maidala Amanikere in Tumkur Taluk.

Sl. No.	Items of work	Per	Quantity	Rate in word and figures
	I Earthwork to channel.			Rs. a. p.
1	Cutting channel and forming spoil bank ...	C.yd.	2,748	
2	Embankment (earth got from pits) ...	"	13,681	
3	Turfing	S.yd.	3,583	
4	Jungle clearing roots entirely grubbed up ...	L. S.	...	
5	Supplying and fixing mile stones figuring and painting, etc., complete.	Each	3	
6	Do furlong stones ...	"	17	
7	Do grade stones ...	"	57	
8	Do bed grade stones ...		57	
	II Constructing madaboys six. Required details for each madaboy.			
1	Earthwork excavation ...	C.yd.	4	
2	Stone jelly concrete in surki mortar ...	C.ft.	56	
3	Burnt stone in surki mortar ...	"	39	
4	Burnt stone slabs 6" roughly dressed ...	S.ft.	33	
5	Pointing with surki mortar ...	Sqr.	...	
6	Teak plug rod with locking arrangement and drilling of plug hole.	L. S.	...	
7	Cast iron pipe 12 feet long from 4" to 6" diar. ...	Each	1	

Sl. No.	Items of work	Per	Quantity	Rate in words and figures
	III Constructing relieving weir No. 1 in 2/1.			Rs. a. p.
1	Earthwork excavation ..	C.yd.	71	
2	Stone jelly concrete in surki mortar	C.ft.	132	
3	Burnt stone in surki mortar ...	,,	1,122	
4	Burnt stone slabs 6" roughly dressed ...	S.ft.	147	
5	Pointing with surki mortar ..	Sqr.	10·46	
6	Rough stone with jelly backing and wedging ...	C.yd.	46	
7	Pointing with cement ...	Sqr.	1·25	
8	Earthwork excavating and filling for facilitating pointing.	L. S.	...	
	IV Joggle weirs No. 2 & 3 in 6/1 and 2/3. (Details for each relieving wear.)			
1	Earthwork excavation ..	C.yd.	68	
2	Stone jelly concrete in surki mortar ...	C.ft.	110	
3	Burnt size stone in surki mortar ...	,,	578	
4	Burnt stone slabs 6" roughly dressed ...	S.ft.	105	
5	Plastering with surki mortar ...	Sqr.	5·64	
6	Rough stone work new with jelly backing and wedging.	C.yd.	12	
7	Pointing with cement	Sqr.	0·65	
8	Approach and draft clearing of cross drainate and using the same for bank.	L. S.	..	
9	Joggle joints	L. S.	...	
	V Drop of 2'-9" (ten drops required). Details for each drop.			
1	Earthwork excavation	C.yd.	22	
2	Stone jelly concrete in surki mortar ...	C.ft.	71	
3	Burnt stone in surki mortar	,,	146	
4	Pointing with surki mortar	Sqr.	1·51	
5	Burnt stone slabs 6" roughly dressed ...	S.ft.	33	
6	Rough stone work with jelly backing and wedging.	C.yd.	16	

N. G. KRISHNA IYENGAR,
Executive Engineer.

MYSORE RAILWAYS.

MYSORE DIVISION—OPEN LINES.

Notification, dated the 4th November 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Senior Executive Engineer, Open Line Division, Mysore Railways, Mysore, up to 4 P.M., on Saturday the 25th November 1933, from Contractors who are willing to do the earth work in the Central Workshops area.

2. Every tender must be accompanied by an earnest money of Rs. 500 which should be paid to the Auditor, Mysore Railways, Mysore, and the receipt thereof enclosed along with the tender.

3. Tenders should be submitted in special forms which can be obtained from the Senior Executive Engineer, Mysore Railways, Mysore, on payment of rupee one, which amount is not refundable under any circumstances.

4. Tenders which give rates as per estimate rates or so much per cent above or below estimate rates, will not be considered. The rates should be noted both in figures and words.

5. The name of the accepted tenderer will be posted on the Notice Board of the Senior Executive Engineer's Office as soon as it is approved by the Superintendent, Way and Works, Mysore Railways. No enquiries regarding the acceptance or rejection of a tender will be replied.

6. The earnest money of the unsuccessful tenderers will be returned as soon as possible after the tenders are disposed of while that of the successful tenderer will be accepted as part payment towards the security deposit due as per para 7 *infra*.